

# OSHA Erection Procedure for Clip Connections

## OSHA Erection Procedure for Clip Connections

OSHA Steel Erection Procedures require Beam Connections that share common Bolts on either side of a Structural Member, that one Beam must remain partially connected while the Adjacent Beam is connected. The erection steps below must be followed to comply with OSHA requirements.

### NOTE:

No additional Framing Members, Bar Joist, Bracing or any additional loads are to be applied to Beams until final adjustment and Bolt tightening thru STEP 4.

